

ROADWAY IMPROVEMENTS

EVALUATION MATRIX

Evaluation Criteria	ALTERNATIVES	
	'No-Build' Alternative	Recommended 'Build' Alternative
Residential Relocations		
Number of Parcels Potentially Impacted	0	17
Number of Residences Relocated	0	17
Business Relocations		
Number of Parcels Potentially Impacted	0	6
Number of Businesses Relocated	0	0
Unimproved Properties Impacted	0	3
Community Facilities		
Number of Parcels Potentially Impacted	0	0
Number of Facilities Relocated	0	0
Section 4(f) / Public Lands		
Number of Sites Potentially Impacted	0	0
Historic/Archeological		
Number of NRHP-eligible Historic Sites Potentially Impacted	0	0
Number of Archeological Sites Potentially Impacted	0	0
Primary Wetland Area (acres impacted, does not	0	2.04
Secondary Wetland Area (acres impacted, does not	0	11.87
Aquatic Preserves / Outstanding Florida Waters	N/A	N/A
Wild and Scenic Rivers (Impacted)	N/A	N/A
Floodplains encroachment	N/A	N/A
Threatened and Endangered Species (Wood Stork SFH potentially impacted)	0	0
Water Quality	No change	Improved water quality; stormwater runoff will be treated in dry ditch or existing wet pond
Farmlands (acres impacted, no ponds)	N/A	N/A
Noise (neighborhoods impacted)	0	2
Potential Contamination Sites		
Number of High Risk Contamination Sites	0	0
Number of Medium Risk Contamination Sites	0	0
Utilities		
Utilities Poles Impacted (distribution, transmission)	0	12
Traffic Service, Operations, Access	Medium	High
Constructability (high, moderate, low)	0	Moderate
Costs Estimates		
Construction	\$0	\$10,355,530
Design	\$0	\$1,800,000
Right-of-Way Acquisition (roadway and ponds)	\$0	\$8,199,000
Construction Engineering and Inspection (CEI)	\$0	\$1,035,553
Noise Barriers	\$0	\$709,440
Utility Relocations (overhead transmission poles)	\$0	\$840,000
Mitigation Cost (includes ponds)	\$0	\$1,773,155
Total Costs Estimate	\$0	\$24,712,678

